

GPS #: 0193R1

Date Destroyed:

Date Revised: 4/19/2001

Benchmark Designation:

OCS Index Map: 4LA

Page/Grid: 828/B-3

City / Location: Midway City

Scale Factor: 0.99997977

Ellipsoid Red. Factor: 1.00000360

Combination Factor: 0.99998343

Convergence Angle: -00 56 58.41969

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 41.23958	117 58 40.76496	2218983.634	6036387.946	
2007.00	33 44 41.25583	117 58 40.78183	2218985.30	6036386.55	

References: OCS SURVEY FILE # 93/94-3N, CR 2001-0821

Description:

FD PUNCHED SPIKE AND 1 1/2" OCS BRASS WASHER STAMPED "0193R1 3-01" FLUSH, IN LIEU OF PUNCHED SPIKE WITH OCS BRASS TAG STAMPED "GPS 0193 11-93". MONUMENT WAS RESET PER CORNER RECORD # 2001-821. MONUMENT IS LOCATED AT THE INTER OF BOLSA AVE. AND PURDY ST.

