

GPS #: **0195**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 832/D-7

City / Location: Unin., Orange County

Scale Factor: 0.99997557

Ellipsoid Red. Factor: 0.99992253

Combination Factor: 0.99989811

Convergence Angle: -00 46 14.51752

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 34.64702	117 39 09.00596	2204703.267	6135151.994	1618.885
2007.00	33 42 34.66358	117 39 09.02178	2204704.96	6135150.68	

References: OCS FILE # OT 94/5-10N, GEODETIC UNIT

Description:

FD 3 1/4" BRASS DISK STAMPED "I-178" SET IN 6" DIA. CONC. COLLAR, FLUSH WITH GROUND, LOCATED FROM THE INTER OF MODJESKA CANYON RD. AND SANTIAGO CANYON RD., PROCEED SE'LY ALONG SANTIAGO CANYON RD. 0.9 MILE TO THE ADDRESS OF 17521 SANTIAGO CANYON RD. MONUMENT IS LOCATED ON TOP OF A HILL APPROX. 2000' W'LY.

