

GPS #: 0207

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 4LB

Page/Grid: 826/G-5

City / Location: Seal Beach

Scale Factor: 0.99997897

Ellipsoid Red. Factor: 1.00000395

Combination Factor: 0.99998293

Convergence Angle: -01 00 39.73334

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 44 17.95340	118 05 23.50671	2217212.032	6002342.497	-82.621
2007.00	33 44 17.96974	118 05 23.52383	2217213.71	6002341.08	

References: NGS PID# DY2646, RSB 150/1-9

Description:

FD 3 1/2" N.G.S. DISK STAMPED "DONE 1974" SET IN TOP OF 12" DIA. CONC. POST FLUSH WITH GROUND SURFACE LOCATED 0.4 MILE SOUTH FROM THE INTER OF SEAL BEACH BLVD. AND PACIFIC COAST HWY., ON RIGHT SIDE, JUST AFTER PASSING OVER AN OVERPASS.

