

**GPS #:** **0209**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 802/A-3

City / Location: Unin., Orange County

Scale Factor: 0.99998563

Ellipsoid Red. Factor: 0.99993470

Combination Factor: 0.99992033

Convergence Angle: -00 46 46.55996

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 21.44529	117 40 07.31609	2233757.424	6130620.994	1366.529
2007.00	33 47 21.46168	117 40 07.33241	2233759.10	6130619.64	

References: OCS SURVEY FILE # G93/94-12N

**Description:**

AKA CONTROL STATION "HIC" - FD 5/8" REBAR, DOWN 0.8'. TO REACH THE STATION FROM THE INTER OF SILVERADO CANYON RD. AND BLACKSTAR CANYON RD., GO NORTH ALONG BLACK STAR CANYON RD. 1.1 MILES TO AN IRON GATE (US FORESTRY LOCK), CONTINUE THRU GATE 0.55 MILE TO A SHARP RIGHT INTO THE CANYON. CONTINUE ALONG RD. EAST 0.9 MILE TO A LOCKED GATE ON THE LEFT (SCE KEY), PROCEED THRU GATE AND UPHILL ALONG DIRT RD. 0.85 MILE TO SAID STATION 3' WEST OF THE HINGEPOINT.

