

GPS #: 0211

Date Destroyed: 7/25/2000

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 798/F-3

City / Location: Garden Grove

Scale Factor: 0.99998655

Ellipsoid Red. Factor: 1.00000060

Combination Factor: 0.99998715

Convergence Angle: -00 55 54.22212

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 45.15956	117 56 43.93965	2237410.374	6046554.058	-12.497
2007.00	33 47 45.17582	117 56 43.95666	2237412.04	6046552.65	

References: NGS PID# DX4774, RSB 149/21-36

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 3 1/2" BRASS N.G.S. DISK STAMPED "LA SE BASE 2 1974" FLUSH IN GROUND LOCATED, IN THE NW CORNER OF ROSIER PRESCHOOL.