

GPS #: **0216**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 802/B-2

City / Location: Unin., Orange County

Scale Factor: 0.99998670

Ellipsoid Red. Factor: 0.99991518

Combination Factor: 0.99990188

Convergence Angle: -00 46 29.79722

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 47 48.97882	117 39 36.81162	2236505.429	6133232.986	1774.330
2007.00	33 47 48.99526	117 39 36.82796	2236507.11	6133231.63	

References: OCS SURVEY FILE # G93/94-12N

Description:

AKA CONTROL STATION "SUSIE" - FD 2 1/2" BRASS CAP STAMPED "SUSIE 8/11/82" IN CONC. COLLAR, UP 0.3'. TO REACH THE STATION FROM THE INTER OF SILVERADO CANYON RD. AND BLACKSTAR CANYON RD., GO NORTH ALONG BLACK STAR CANYON RD. 1.1 MILES TO AN IRON GATE (US FORESTRY LOCK), CONTINUE THRU GATE 0.55 MILE TO A SHARP RIGHT INTO THE CANYON. CONTINUE ALONG RD. EAST 3.45 MILES TO SAID STATION LOCATED 100'+/- BEFORE A CATTLE XING AND ENTRANCE TO CLEVELAND NATIONAL FOREST AREA AND 80'+/- S'LY FROM THE RD.

