

**GPS #:** 0219

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 772/D-6

City / Location: Unin., Orange County

Scale Factor: 0.99998983

Ellipsoid Red. Factor: 0.99987738

Combination Factor: 0.99986722

Convergence Angle: -00 45 54.70953

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 49 07.13322	117 38 32.95982	2244332.458	6138726.641	2564.188
2007.00	33 49 07.14977	117 38 32.97635	2244334.15	6138725.27	

References: OCS SURVEY FILE # G93/94-12N

**Description:**

AKA CONTROL STATION "CURARE" - FD 2" I.P. WITH 2 1/4" BRASS CAP STAMPED "CURARE 82" UP 0.2' IN DIRT. TO REACH THE STATION FROM THE INTER OF SILVERADO CANYON RD. AND BLACKSTAR CANYON RD., GO NORTH ALONG BLACK STAR CANYON RD. 1.1 MILES TO AN IRON GATE (US FORESTRY LOCK), CONTINUE THRU GATE 0.55 MILE TO A SHARP RIGHT INTO THE CANYON. CONTINUE ALONG RD. 6.8 MILES TO REFERENCE MARKER "PI-219" ON SIDE OF RD. TURN RIGHT ON DIRT TRAIL AND GO 350' +/- TO SAID STATION.

