

**GPS #:** **0220**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 772/F-7

City / Location: Unin., Orange County

Scale Factor: 0.99998905

Ellipsoid Red. Factor: 0.99984247

Combination Factor: 0.99983153

Convergence Angle: -00 45 20.18505

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 48 48.14652	117 37 30.13292	2242343.021	6144001.685	3293.891
2007.00	33 48 48.16304	117 37 30.14937	2242344.71	6144000.32	

References: OCS SURVEY FILE # G93/94-12N

**Description:**

AKA CONTROL STATION "MINE II" - FD 2" I.P. WITH 2 1/4" PUNCHED BRASS CAP STAMPED "MINE II" UP 0.2' IN DIRT. TO REACH THE STATION FROM THE INTER OF SILVERADO CANYON RD. AND BLACKSTAR CANYON RD., GO NORTH ALONG BLACK STAR CANYON RD. 1.1 MILES TO AN IRON GATE (US FORESTRY LOCK), CONTINUE THRU GATE 0.55 MILE TO A SHARP RIGHT INTO THE CANYON. CONTINUE ALONG RD. 6.8 MILES TO AN IRON GATE (US FORESTRY LOCK), PROCEED THRU GATE ON DIRT RD. 0.05 MILE TO FORK WHICH IS THE MAIN DIVIDE RD. BEAR RIGHT TO ANOTHER IRON GATE (US FORESTRY LOCK), CONTINUE THRU GATE PAST BEEKS PLACE AND CONTINUE ALONG RD. 1.25 MILES. WALK 200' +/- UP SMALL HILL TO SAID STATION.

