

GPS #: **0221**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 772/E-5

City / Location: Unin., Orange County

Scale Factor: 0.99999159

Ellipsoid Red. Factor: 0.99987699

Combination Factor: 0.99986858

Convergence Angle: -00 45 42.83532

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 49 49.63649	117 38 11.35139	2248604.203	6140606.753	2572.259
2007.00	33 49 49.65299	117 38 11.36793	2248605.89	6140605.38	

References: OCS SURVEY FILE # G93/94-12N

Description:

FD CENTER PORTION OF ALUMINUM DISK (CENTER PUNCHED) IN 2" I.P., DOWN 1.5'. LOCATED IN A N'LY DIRECTION FROM THE INTER OF SILVERADO CANYON RD. AND BLACKSTAR CANYON RD.; SET 20' OFF A DIRT RD., OFF BLACK STAR CANYON, ON THE EDGE OF THE CLEVELAND NATIONAL FOREST.

