

GPS #: 0226

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 802/B-5

City / Location: Unin., Orange County

Scale Factor: 0.99998417

Ellipsoid Red. Factor: 0.99991232

Combination Factor: 0.99989649

Convergence Angle: -00 46 29.79784

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 46 42.99907	117 39 36.81275	2229836.588	6133142.687	1834.193
2007.00	33 46 43.01572	117 39 36.82898	2229838.29	6133141.34	

References: OCS SURVEY FILE # G93/94-12N

Description:

AKA CONTROL STATION "STAR" - FD 3 1/2" BRASS U. S. C. & G. S. DISK STAMPED "STAR 1928" CEMENTED FLUSH IN SANDSTONE ROCK. TO REACH THE STATION FROM THE INTER OF SILVERADO CANYON RD. AND BLACKSTAR CANYON RD., PROCEED NORTH ALONG BLACKSTAR CANYON RD. 0.65 MILE TO BAKER CANYON RD. ON RIGHT "FLYING B RANCH". TURN RIGHT AND PROCEED 0.30 MILE TO A DIRT RD. ON LEFT WITH A LOCKED BARBED WIRE FENCE GATE (DA1 KEY). PROCEED THRU GATE, TAKE FIRST LEFT AND GO 0.30 MILE TO A CREEK BED. CROSS CREEK BED AND CONTINUE N'LY ON SAME RD. 1.15 MILES THRU A GATE TO A THREE-WAY FORK OF DIRT RD.S. TAKE THE FAINT RD. TO THE RIGHT THAT LEADS MOST N'LY, THEN E'LY AND CONTINUE ALONG SAID RD. 0.45 MILE WINDING UPHILL AND AROUND THE HILL TO A "T" INTER WITH A DIRT RD. LOCATED IN A SANDSTONE BOULDER FIELD AREA. TURN LEFT AND GO UP STEEP AND BUMPY HILL 0.15 MILE TO THE TOP OF A PROMINENT KNOLL JUST RIGHT AND 50'+/- E'LY OF THE RD. SAID STATION IS LOCATED ON KNOLL.

