

GPS #: 0232

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 796/J-1

City / Location: Long Beach, Los Angeles Co.

Scale Factor: 0.99998968

Ellipsoid Red. Factor: 1.00000351

Combination Factor: 0.99999319

Convergence Angle: -00 59 58.46803

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 49 03.39545	118 04 08.41298	2245949.731	6009186.509	-73.415
2007.00	33 49 03.41152	118 04 08.43062	2245951.38	6009185.05	

References: RSB 149/21-36

Description:

FD TACK IN LEAD WITH 1 1/4" BRASS TAG STAMPED "OCS CC 14" IN CONC. MEDIAN FLUSH WITH SURFACE, LOCATED AT THE APPARENT CENTERLINE INTER OF WARDLOW RD. AND COYOTE CREEK.

