

**GPS #:** **0239**

Date Destroyed:

Date Revised: 4/23/1996

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 832/D-6

City / Location: Unin., Orange County

Scale Factor: 0.99997694

Ellipsoid Red. Factor: 0.99994947

Combination Factor: 0.99992642

Convergence Angle: -00 46 06.13261

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 17.18742	117 38 53.74728	2208985.604	6136498.557	1055.867
2007.00	33 43 17.20402	117 38 53.76303	2208987.30	6136497.25	

References: A/NE-IRV, 1383, OCS FILE # OT 94/5-10N

**Description:**

FD 1 1/2" AXLE WITH PUNCH MARK, DOWN 0.5', LOCATED FROM THE INTER OF SANTIAGO CANYON RD. AND MOJESKA CANYON RD., PROCEED NW'LY 0.3 MILES ALONG SANTIAGO CANYON RD. TO SAID MONUMENT LOCATED 1' +/- OFF THE W'LY EDGE OF RD. AND 170' +/- NW'LY OF A STEEL AND CHAIN LINK GATE AND 85' +/- NW'LY OF A POWER POLE WHICH IS THE SECOND TO LAST POWER POLE ON SW'LY SIDE OF SANTIAGO CANYON RD. BEFORE TOWER LINES CROSS SANTIAGO CANYON RD. HEADING NW.

