

GPS #: 0251

Date Destroyed:
Date Revised: 11/9/1998
Benchmark Designation:
OCS Index Map: 6LA
Page/Grid: 951/G-2
City / Location: Laguna Niguel

Scale Factor: 0.99996123
Ellipsoid Red. Factor: 0.99999570
Combination Factor: 0.99995696
Convergence Angle: -00 48 02.17451

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 00.01564	117 42 24.91779	2146852.731	6117791.823	-56.480
2007.00	33 33 00.03268	117 42 24.93383	2146854.47	6117790.49	

References: OCS SURVEY FILE # O93/94-GN

Description:

FD 2 1/2" PUNCHED BRASS DISK DOWN 1.0' IN WELL MONUMENT. TO REACH THE STATION FROM THE MAIN ENTRANCE TO LAGUNA NIGUEL PARK ON LA PAZ RD., PROCEED THRU PARK GATE AND TURN LEFT AT FIRST PARK RD. FOLLOW THE RD. HEADING S'LY 0.2+/- MILE TO STOP SIGN. TURN LEFT AND GO UPHILL 0.1 MILE AND PROCEED TO THE LOCKED GATE (DA1 KEY) WHICH IS THE ENTRANCE ON TO THE DAM. PROCEED THRU GATE AND ON TO THE DAM RD. TO SAID STATION WHICH IS 365'+/- FROM THE PARK RD.

