

GPS #: **0278**

Date Destroyed: 11/2/2017
Date Revised: 4/23/1996
Benchmark Designation:
OCS Index Map: 5LB
Page/Grid: 862/E-1
City / Location: Unin., Orange County

Scale Factor: 0.99997471
Ellipsoid Red. Factor: 0.99992345
Combination Factor: 0.99989817
Convergence Angle: -00 45 43.30191

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 07.24483	117 38 12.20048	2201869.488	6139913.513	1599.620
2007.00	33 42 07.26148	117 38 12.21618	2201871.19	6139912.21	

References: OCS FILE # OT 94/5-10N, GEODETIC UNIT

Description:

DESTROYED - FD 2 1/2" BRASS OCS DISK STAMPED "MODJESKA 1A 1980" SET IN CONC. COLLAR FLUSH WITH SURFACE. LOCATED FROM THE INTER OF SANTIAGO CANYON RD. AND MODJESKA GRADE RD., PROCEED N'LY ALONG MODJESKA GRADE RD. 0.5 MILES UPHILL TO THE TOP OF RIDGE AND CASA LOMA, ADDRESS #28012 ON LEFT. MONUMENT IS LOCATED 200' +/- S'LY OF CASA LOMA ENTRANCE, ON TOP OF PROMINENT HILL.

