

GPS #: **0309**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 863/C-5

City / Location: Unin., Orange County

Scale Factor: 0.99997189

Ellipsoid Red. Factor: 0.99993592

Combination Factor: 0.99990782

Convergence Angle: -00 43 47.64953

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 33.14103	117 34 41.73883	2192126.710	6157571.666	1341.365
2007.00	33 40 33.15768	117 34 41.75419	2192128.41	6157570.39	

References: OCS SURVEY FILE # O93/94-8

Description:

FD 1" I.P. WITH 1 1/4" OCS BRASS TAG AND BRASS NAIL STAMPED "JBR 94 C GPS 0309", DOWN 0.1' IN DIRT. LOCATED NORTH OF THE INTER OF TRABUCO CANYON RD. AND ROSE CANYON RD.; SET IN DIRT OFF THE WEST EDGE OF ROSE CANYON RD. AND SOUTH OF THE SOUTH END OF A STEEL GUARD RAIL.

