

GPS #: **0322**

Date Destroyed: **7/25/2000**

Date Revised:

Benchmark Designation:

OCS Index Map: **6LB**

Page/Grid: **863/C-5**

City / Location: **Unin., Orange County**

Scale Factor: **0.99997197**

Ellipsoid Red. Factor: **0.99993345**

Combination Factor: **0.99990543**

Convergence Angle: **-00 43 46.08294**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 40 36.14496	117 34 38.88798	2192427.255	6157816.438	1393.127
2007.00	33 40 36.16156	117 34 38.90336	2192428.95	6157815.16	

References: **OCS SURVEY FILE # O93/94-8**

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 1" I.P. WITH 1 1/4" OCS BRASS TAG AND BRASS NAIL STAMPED "JBR 94 D GPS 0322", SET FLUSH IN DIRT. LOCATED NORTH OF THE INTER OF TRABUCO CANYON RD. AND ROSE CANYON RD.; SET IN DIRT OFF THE WEST EDGE OF ROSE CANYON RD. AND SE OF THE NORTH END OF A STEEL GUARD RAIL.