

GPS #: **0364**

Date Destroyed:

Date Revised: 3/23/2000

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 831/B-5

City / Location: Unin., Orange County

Scale Factor: 0.99997816

Ellipsoid Red. Factor: 0.99998324

Combination Factor: 0.99996141

Convergence Angle: -00 49 21.82474

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 43 54.04771	117 44 49.86352	2213128.757	6106475.218	350.121
2007.00	33 43 54.06406	117 44 49.87953	2213130.43	6106473.89	

References: RSB 139/12-14, CR 0939

Description:

AKA "LEDGE" - FD 1 1/2" BRASS TAG WITH BRASS NAIL, NO STAMPING, SET IN CONC. IN ROCK FORMATION, LOCATED FROM THE INTER OF PORTOLA PKWY. AND YALE RD., GO NE'LY ALONG PORTOLA 0.35 MILE TO THE ENTRY OF MM FARMS LOCATED ON THE NORTH SIDE, ADDRESS 4769 PORTOLA. ENTER DRIVE WAY, PASS THRU PRIVATE IRON GATE, GO 300'+/- TO A "Y" IN THE ROAD, TAKE DIRT ROAD ON LEFT AND PROCEED 0.10 MILE THRU AN IRON GATE AND TO ANOTHER "Y" IN THE ROAD. GO LEFT OVER LARGE IRRIGATION DITCH, 0.15 MILE TO A 4 WAY DIRT INTERSECTION. CONTINUE STRAIGHT ON UPHILL ROAD 0.10 MILE TO END OF LARGE CONCRETE LINED IRRIGATION DITCH ON RIGHT AND A "Y" IN ROAD. TURN RIGHT ON ROAD AND PROCEED NE'LY 0.10 MILE PARALLEL WITH A IRRIGATION DITCH, TO A "Y" INTERSECTION. TURN LEFT AND UPHILL 0.05 MILE SW'LY, STOP HERE. SAID STATION IS LOCATED 35'+/- UP THE HILL IN A SE'LY DIRECTION.

