

**GPS #:** 0377R1

Date Destroyed:

Date Revised: 3/20/2013

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 890/A-4

City / Location: Irvine

Scale Factor: 0.99996781

Ellipsoid Red. Factor: 0.99999483

Combination Factor: 0.99996264

Convergence Angle: -00 52 16.23598

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 02.59162	117 50 07.25327	2178003.794	6079132.495	
2007.00	33 38 02.60799	117 50 07.27019	2178005.47	6079131.09	

References: RSB 119/25-29, RSB 251/10-14

**Description:**

RESET 3/20/13 FD 3" CROWNED BRONZED DISK STAMPED "91-90-98-99 RCE 21687" PER RS 2010-1145, IN LIEU OF, 3 1/2" BRASS OCS DISK STAMPED "91 90 98 99" IN CONCRETE COLLAR, FLUSH IN DIRT. DO NOT USE THE PUNCH LOCATED 0.03' EASTERLY FROM THE CENTER OF DISK. THE MONUMENT IS LOCATED FROM THE INTER OF NEWPORT COAST DR. AND BONITA CANYON DR., PROCEED N'LY 230' +/- TO SAID MONUMENT LOCATED ON THE SIDE OF A DIRT HILL, WITNESSED BY 2 WITNESS POSTS.

