

GPS #: 0397

Date Destroyed: 7/26/2000

Date Revised:

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 739/H-7

City / Location: Placentia

Scale Factor: 0.99999749

Ellipsoid Red. Factor: 0.99999403

Combination Factor: 0.99999153

Convergence Angle: -00 52 30.58465

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 52 05.20651	117 50 33.36468	2263200.962	6078225.941	124.724
2007.00	33 52 05.22299	117 50 33.38135	2263202.65	6078224.56	

References: SM 71-5, RSB 149/1-9

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD SPIKE AND O.C.S. WASHER (ILLEGIBLE), ACCEPTED AS SPIKE AND OCS WASHER STAMPED "RCE 6978" PER SM 71-5. STATION IS LOCATED IN THE INTER OF ORANGETHORPE AVE. AND ROSE DR., ALONG THE TANGENT PROD OF ORANGETHORPE AND 49' +/- N'LY FROM THE N'LY END OF THE MEDIAN WITH A RAILRD. CROSSING GATE.