

GPS #: **0447**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 831/E-7

City / Location: Unin., Orange County

Scale Factor: 0.99997579

Ellipsoid Red. Factor: 0.99996149

Combination Factor: 0.99993729

Convergence Angle: -00 48 18.81429

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 41.79586	117 42 55.19850	2205688.586	6116055.770	806.576
2007.00	33 42 41.81223	117 42 55.21440	2205690.26	6116054.45	

References: OCS SURVEY FILE # R92-10A

Description:

FD 3 3/4" OCS ALUMINUM DISK STAMPED "IRV 119" (TWICE), SET IN CONC., FLUSH WITH GROUND. LOCATED IN A NE'LY DIRECTION FROM THE INTER OF SAND CANYON RD. AND PORTOLA PKWY.; SET ON A RIDGE NORTH OF A RETARDING BASIN NEAR CONSTRUCTION SITE OFF PORTOLA PKWY.

