

GPS #: 0460

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 922/E-3

City / Location: Mission Viejo

Scale Factor: 0.99996388

Ellipsoid Red. Factor: 0.99997679

Combination Factor: 0.99994067

Convergence Angle: -00 45 50.41976

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 14.11356	117 38 25.15339	2160128.744	6138262.469	492.387
2007.00	33 35 14.13055	117 38 25.16926	2160130.48	6138261.15	

References: OCS SURVEY FILE # 93/94-2

Description:

FD 1 1/4" BRASS OCS TAG STAMPED "GPS 0207 12-93" WITH BRASS NAIL IN LEAD, FLUSH IN CONC. LOCATED EAST OF THE INTER OF OSO PKWY. AND FELIPE RD.; SET ON THE SOUTH SIDE OF OSO PKWY. ON A 4' WIDE R.C.B. OUTLET, 3' SOUTH OF THE CURB FACE.

