

GPS #: **0461R1**

Date Destroyed:

Date Revised: 4/3/2001

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 708/B-7

City / Location: La Habra

Scale Factor: 1.00000710

Ellipsoid Red. Factor: 0.99999200

Combination Factor: 0.99999917

Convergence Angle: -00 56 55.57240

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 28.65241	117 58 35.58354	2284411.032	6037909.065	
2007.00	33 55 28.66867	117 58 35.60090	2284412.70	6037907.63	

References: RS 92-1117, CR 2001-0692

Description:

FD PUNCHED SPIKE AND "L.A. CO. D.P.W." WASHER FLUSH, IN LIEU OF LARGE PK NAIL AND TAG, NO STAMPING. MONUMENT WAS RESET PER CORNER RECORD # 2001-692. MONUMENT IS LOCATED FROM THE INTER OF BEACH BLVD. AND LAMBERT RD., PROCEED W'LY 0.5 MILE TO SAID STATION BEING 140 +/- EAST OF THE INTER OF LAMBERT RD. AND SUGAR GROVE DR./ GRAYLING AVE., ALONG THE APPARENT CENTERLINE OF LAMBERT RD.

