

GPS #: 0475

Date Destroyed: 7/25/2000

Date Revised:

Benchmark Designation:

OCS Index Map: 3L

Page/Grid: 738/B-2

City / Location: La Habra

Scale Factor: 1.00000450

Ellipsoid Red. Factor: 0.99999589

Combination Factor: 1.00000040

Convergence Angle: -00 56 55.62168

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 54 36.02834	117 58 35.67322	2279092.250	6037813.423	85.715
2007.00	33 54 36.04452	117 58 35.69067	2279093.91	6037811.98	

References: RS 92-1117

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 2" I.P. WITH NAIL AND TAG STAMPED "LS 4599" DOWN 0.5' LOCATED FROM THE INTER OF BEACH BLVD. AND HILLSBOROUGH DR., PROCEED 0.1 MILE E'LY ALONG BEACH BLVD. MONUMENT IS ON THE N'LY SIDE OF BEACH BLVD., 25'+/- N'LY OF THE EDGE OF PAVEMENT.