

GPS #: 0486R1

Date Destroyed: 9/16/2014
Date Revised: 11/1/2007
Benchmark Designation:
OCS Index Map: 1L
Page/Grid: 709/G-6
City / Location: Unin., Orange County

Scale Factor: 1.00000707
Ellipsoid Red. Factor: 0.99998039
Combination Factor: 0.99998747
Convergence Angle: -00 52 40.57819

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 55 26.82996	117 50 51.55070	2283603.500	6077004.896	
2007.00	33 55 26.84665	117 50 51.56744	2283605.21	6077003.51	

References: CR 2003-2063A, 2003-2064B

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 8" PUNCHED SPIKE WITH 1 1/4" BRASS OCS WASHER RESET PER CR 2003-2064B. ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE AND 1 1/2" O.C.S. WASHER FLUSH WITH A.C. SURFACE, AT THE CENTERLINE INTER OF LAMBERT RD./ CARBON CANYON RD. AND VALENCIA AVE., N'LY 20.00' FROM A SPIKE AND WASHER (NO STAMPING).

