

GPS #: 0500

Date Destroyed: 5/16/1997

Date Revised:

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 892/C-1

City / Location: Lake Forest

Scale Factor: 0.99996941

Ellipsoid Red. Factor: 0.99997290

Combination Factor: 0.99994232

Convergence Angle: -00 46 29.91451

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 04.16127	117 39 37.02506	2183461.186	6132497.457	566.429
2007.00	33 39 04.17814	117 39 37.04092	2183462.91	6132496.14	

References: OCS SURVEY FILE # G93/94-13N

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0500" FLUSH IN A.C. - LOCATED FROM THE INTER OF EL TORO RD. AND NORMANDALE DR., PROCEED S'LY ALONG EL TORO RD. 0.3 MILE TO SUMMERWOOD WAY ON THE LEFT. STATION IS AT MOST S'LY TIP OF PAINTED ARROW IN THE LEFT TURN POCKET FOR SUMMERWOOD WAY.

NO
LOCATION
MAP