

GPS #: 0558

Date Destroyed:

Date Revised: 7/1/1997

Benchmark Designation:

OCS Index Map: 5LB

Page/Grid: 892/A-3

City / Location: Lake Forest

Scale Factor: 0.99996856

Ellipsoid Red. Factor: 0.99997542

Combination Factor: 0.99994398

Convergence Angle: -00 46 59.94706

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 38 31.84166	117 40 31.67764	2180257.470	6127833.211	513.706
2007.00	33 38 31.85849	117 40 31.69342	2180259.19	6127831.90	

References: OCS SURVEY FILE # G93/94-13N

Description:

FD FOUR 2' TANGENT OVER C-NAIL TIES WITH 3/4" BRASS O.C.S. TIE TAGS ON A.C. SURFACE, ACTUAL SURVEY POINT FALL ON MANHOLE - LOCATED FROM THE INTER OF EL TORO RD. AND ALISO PARK DR., PROCEED N'LY ALONG ALISO PARK DR. TO RICHFORD DR., TURN LEFT AND CONTINUE N'LY ALONG RICHFORD TO ELSBERRY WAY, TURN LEFT AND CONTINUE S'LY ALONG ELSBERRY WAY 100'+/- TO A 3' DIA. SEWER MANHOLE AND SAID STATION.

