

GPS #: 0560

Date Destroyed: 5/11/2017

Date Revised: 5/6/2003

Benchmark Designation:

OCS Index Map: 1L

Page/Grid: 769/D-1

City / Location: Placentia

Scale Factor: 0.99999615

Ellipsoid Red. Factor: 0.99999596

Combination Factor: 0.99999211

Convergence Angle: -00 53 50.73971

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 51 35.17481	117 52 59.22415	2260355.808	6065880.428	84.413
2007.00	33 51 35.19142	117 52 59.24140	2260357.51	6065879.00	

References: CR 2003-1000

Description:

FOUND PUNCHED SPIKE AND WASHER STAMPED "CALTRANS", FLUSH IN AC. MONUMENT IS LOCATED IN THE INTERSECTION OF ORANGETHORPE AVE. AND PLACENTIA AVE.

