

GPS #: 0565R1

Date Destroyed:

Date Revised: 5/25/2015

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 889/J-2

City / Location: Irvine

Scale Factor: 0.99996941

Ellipsoid Red. Factor: 1.00000314

Combination Factor: 0.99997254

Convergence Angle: -00 52 28.95415

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 03.80068	117 50 30.39752	2184219.852	6077270.308	
2007.00	33 39 03.81717	117 50 30.41436	2184221.54	6077268.91	

References: CR 2003-1003, CR 2013-0239, CR 2014-0213, CR 2014-1894

Description:

FOUND GEAR SPIKE AND WASHER STAMPED "PLS 7564" FLUSH PER CR 2014-1894 IN LIEU OF GEAR SPIKE AND WASHER STAMPED "JOHSON FRANK & ASSOCIATES LS 4215", FLUSH IN AC. MONUMENT IS LOCATED IN THE INTERSECTION OF CAMPUS DR. AND W. PELTASON RD./ BRIDGE RD.

