

GPS #: 0567

Date Destroyed:

Date Revised: 5/6/2003

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 952/C-5

City / Location: San Juan Capistrano

Scale Factor: 0.99995974

Ellipsoid Red. Factor: 0.99998887

Combination Factor: 0.99994861

Convergence Angle: -00 46 29.98710

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 33.68884	117 39 37.15717	2137932.685	6131870.422	232.624
2007.00	33 31 33.70602	117 39 37.17283	2137934.44	6131869.12	

References: CR 1998-0090, CR 2003-1079

Description:

FOUND GEAR SPIKE AND WASHER STAMPED "LS 5411", FLUSH IN AC. MONUMENT IS LOCATED IN THE CUL-DE-SAC OF CANYON CREST RD.

