

GPS #: 0603

Date Destroyed: 7/26/2000
Date Revised: 7/1/1997
Benchmark Designation:
OCS Index Map: 6LA
Page/Grid: 891/H-6
City / Location: Lake Forest

Scale Factor: 0.99996656
Ellipsoid Red. Factor: 0.99998613
Combination Factor: 0.99995269
Convergence Angle: -00 47 38.58708

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 37 12.03507	117 41 41.99390	2172273.305	6121777.240	289.875
2007.00	33 37 12.05214	117 41 42.01004	2172275.05	6121775.90	

References: OCS SURVEY FILE # G93/94-13N

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 1 1/2" BRASS O.C.S. TAG IN EPOXY, NO STAMPING, FLUSH ON A.C. SURFACE - LOCATED FROM THE INTER OF EL TORO RD. AND MUIRLANDS BLVD., PROCEED SE'LY 0.3 MILE ALONG MUIRLANDS BLVD. TO SAID STATION LOCATED AT THE APPARENT B.C.