

GPS #: 0604

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 5LA

Page/Grid: 890/E-1

City / Location: Irvine

Scale Factor: 0.99997002

Ellipsoid Red. Factor: 0.99998960

Combination Factor: 0.99995962

Convergence Angle: -00 50 59.34755

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 39 26.56313	117 47 47.33338	2186312.976	6091087.385	217.339
2007.00	33 39 26.57987	117 47 47.34995	2186314.69	6091086.01	

References: NGS PID# DX4415, RSB 150/10-23

Description:

FD U.S.C. & G.S. BRASS DISK STAMPED "FRENCH 1928" SET IN A LARGE BOULDER, UP 2.0' ABOVE GROUND, SET ON TOP OF PROMINENT HILL 0.3+/- MILE S'LY FROM INTER OF 405 FREEWAY AND UNIVERSITY DR.

