

GPS #: 0606

Date Destroyed: 8/31/2012
Date Revised: 7/1/1997
Benchmark Designation:
OCS Index Map: 6LA
Page/Grid: 891/H-7
City / Location: Lake Forest

Scale Factor: 0.99996592
Ellipsoid Red. Factor: 0.99998720
Combination Factor: 0.99995313
Convergence Angle: -00 47 41.37410

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 36 45.21055	117 41 47.06566	2169568.128	6121310.779	267.381
2007.00	33 36 45.22759	117 41 47.08190	2169569.87	6121309.43	

References: OCS SURVEY FILE # G93/94-13N

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0606" FLUSH ON A.C. SURFACE - LOCATED AT THE INTER OF LOS ALISOS BLVD. AND ROCKFIELD BLVD., IN THE POINT OF THE MOST N'LY PAINTED TURN ARROW, IN THE EAST BOUND ROCKFIELD BLVD. TURNING LN. TO NORTH BOUND LOS ALISOS BLVD.

NO
LOCATION
MAP