

GPS #: 0610

Date Destroyed:

Date Revised: 1/2/2010

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 921/F-2

City / Location: Aliso Viejo

Scale Factor: 0.99996454

Ellipsoid Red. Factor: 0.99999148

Combination Factor: 0.99995603

Convergence Angle: -00 48 19.62554

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 44.47502	117 42 56.67479	2163511.901	6115338.097	
2007.00	33 35 44.49213	117 42 56.69101	2163513.65	6115336.75	

References: OCS SURVEY FILE # G93/94-13N, CR 2009-2196, CR 2009-2457

Description:

FD SPIKE AND WASHER STAMPED "LS 5301" FLUSH, IN LIEU OF PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0610" FLUSH ON A.C. SURFACE - LOCATED AT THE INTER OF MOULTON PKWY. AND GLENWOOD DR./INDIAN CREEK LN., IN THE POINT OF THE MOST W'LY PAINTED TURN ARROW, IN THE LEFT TURN LN. ALONG NORTH BOUND MOULTON PKWY. TURNING TO WEST BOUND GLENWOOD DR.

