

GPS #: **0612**

Date Destroyed: **7/25/2000**
Date Revised: **7/1/1997**
Benchmark Designation:
OCS Index Map: **6LA**
Page/Grid: **921/G-4**
City / Location: **Laguna Hills**

Scale Factor: **0.99996338**
Ellipsoid Red. Factor: **0.99999415**
Combination Factor: **0.99995754**
Convergence Angle: **-00 48 05.72716**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 34 50.77009	117 42 31.38282	2158054.049	6117401.341	122.273
2007.00	33 34 50.78722	117 42 31.39908	2158055.80	6117399.99	

References: OCS SURVEY FILE # G93/94-13N

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0612" FLUSH ON A.C. SURFACE - LOCATED AT THE INTER OF ALICIA PKWY. AND RAMONA ST., IN THE POINT OF THE PAINTED TRAFFIC LN. CHANGE ARROW, AT THE PROD OF RAMONA ST. ON THE W'LY SIDE OF ALICIA PKWY.