

GPS #: **0617**

Date Destroyed: **3/22/1999**

Date Revised: **7/1/1997**

Benchmark Designation:

OCS Index Map: **6LA**

Page/Grid: **921/F-7**

City / Location: **Laguna Niguel**

Scale Factor: **0.99996213**

Ellipsoid Red. Factor: **0.99999482**

Combination Factor: **0.99995696**

Convergence Angle: **-00 48 19.39656**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 48.50848	117 42 56.25810	2151790.934	6115208.579	108.153
2007.00	33 33 48.52556	117 42 56.27410	2151792.68	6115207.25	

References: OCS SURVEY FILE # G93/94-13N

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0617" FLUSH IN A.C. SURFACE - LOCATED AT THE INTER OF ALICIA PKWY. AND AVILA RD., IN THE LEFT TURN LN. OF SOUTH BOUND ALICIA PKWY., 200'+/- N'LY FROM THE S'LY TIP OF THE MEDIAN IN THE CENTER OF ALICIA PKWY.