

**GPS #:** **0622**

**Date Destroyed:** **7/25/2000**

**Date Revised:** **7/1/1997**

**Benchmark Designation:**

**OCS Index Map:** **6LA**

**Page/Grid:** **951/E-1**

**City / Location:** **Laguna Niguel**

**Scale Factor:** **0.99996126**

**Ellipsoid Red. Factor:** **0.99999863**

**Combination Factor:** **0.99995989**

**Convergence Angle:** **-00 48 30.10146**

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 33 01.92095	117 43 15.73864	2147105.681	6113493.880	28.668
2007.00	33 33 01.93806	117 43 15.75477	2147107.43	6113492.54	

**References:** OCS SURVEY FILE # G93/94-13N

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0622" FLUSH IN A.C. SURFACE - LOCATED IN ALISO WOODS CANYON REGIONAL PARK. FROM THE INTER OF ALICIA PKWY. AND AWMA RD., PROCEED W'LY ALONG AWMA RD. 0.1 MILE TO AN OPEN COUNTY PARK GATE. PROCEED THRU SAID GATE AND CONTINUE S'LY ALONG A.C. RD. 0.1 MILE TO SAID STATION LOCATED 4.5' E'LY OF THE W'LY EDGE OF THE A.C. RD.

NO  
LOCATION  
MAP