

GPS #: **0624**

Date Destroyed: **7/25/2000**

Date Revised: **7/1/1997**

Benchmark Designation:

OCS Index Map: **6LA**

Page/Grid: **951/E-3**

City / Location: **Laguna Niguel**

Scale Factor: **0.99996074**

Ellipsoid Red. Factor: **0.99999971**

Combination Factor: **0.99996045**

Convergence Angle: **-00 48 41.78427**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 33.00721	117 43 36.99875	2144208.898	6111653.383	6.125
2007.00	33 32 33.02425	117 43 37.01491	2144210.64	6111652.04	

References: OCS SURVEY FILE # G93/94-13N

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 2" I.P. WITH PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0624" FLUSH IN DIRT - LOCATED IN ALISO WOODS CANYON REGIONAL PARK. FROM THE INTER OF ALICIA PKWY. AND AWMA RD., PROCEED W'LY ALONG AWMA RD. 0.1 MILE TO AN OPEN COUNTY PARK GATE. PROCEED THRU SAID GATE AND CONTINUE S'LY ALONG A.C. RD. 1.05 MILES TO A CONC. DROP STRUCTURE/RD. ON THE E'LY SIDE. PROCEED THRU A LOCKED CHAINED GATE (DA1 KEY), THEN CROSS THE DROP STRUCTURE TO A DIRT RD. ON THE NORTH SIDE. PROCEED NORTH ALONG SAID DIRT RD. 0.35 MILE, THEN HIKE E'LY 175'+/- TO SAID STATION.