

GPS #: 0626

Date Destroyed: 7/25/2000
Date Revised: 7/1/1997
Benchmark Designation:
OCS Index Map: 6LA
Page/Grid: 951/C-3
City / Location: Laguna Niguel

Scale Factor: 0.99996064
Ellipsoid Red. Factor: 1.00000017
Combination Factor: 0.99996081
Convergence Angle: -00 49 05.83475

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 27.35187	117 44 20.76530	2143690.020	6107941.214	-3.474
2007.00	33 32 27.36879	117 44 20.78135	2143691.75	6107939.88	

References: OCS SURVEY FILE # G93/94-13N

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 2" I.P. WITH PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0626" FLUSH IN DIRT - LOCATED IN ALISO WOODS CANYON REGIONAL PARK. FROM THE INTER OF ALICIA PKWY. AND AWMA RD., PROCEED W'LY ALONG AWMA RD. 0.1 MILE TO AN OPEN COUNTY PARK GATE. PROCEED THRU SAID GATE AND CONTINUE S'LY ALONG A.C. RD. 1.5 MILES TO A DIRT RD. AND A LOCKED CHAINED COUNTY PARK GATE (DA1 KEY) ON THE W'LY SIDE, PROCEED THRU THE GATE AND PARK NEAR THE RANGER OFFICE TRAILER. HIKE S'LY 300'+/- ALONG THE TOE OF THE W'LY SLOPE TO SAID STATION.