

GPS #: **0628**

Date Destroyed: **7/25/2000**

Date Revised: **7/1/1997**

Benchmark Designation:

OCS Index Map: **6LA**

Page/Grid: **951/C-3**

City / Location: **Laguna Niguel**

Scale Factor: **0.99996038**

Ellipsoid Red. Factor: **1.00000068**

Combination Factor: **0.99996106**

Convergence Angle: **-00 49 05.94523**

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 12.33770	117 44 20.96634	2142172.835	6107902.525	-14.157
2007.00	33 32 12.35467	117 44 20.98241	2142174.57	6107901.19	

References: **OCS SURVEY FILE # G93/94-13N**

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 2" I.P. WITH PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0628" FLUSH IN DIRT - LOCATED IN ALISO WOODS CANYON REGIONAL PARK. FROM THE INTER OF ALICIA PKWY. AND AWMA RD., PROCEED W'LY ALONG AWMA RD. 0.1 MILE TO AN OPEN COUNTY PARK GATE. PROCEED THRU SAID GATE AND CONTINUE S'LY ALONG A.C. RD. 1.05 MILES TO A CONC. DROP STRUCTURE/RD. ON THE E'LY SIDE. PROCEED THRU A LOCKED CHAINED GATE (DA1 KEY), THEN CROSS THE DROP STRUCTURE AND GO 0.1 MILE AND TURN RIGHT ONTO DIRT RD. ON THE SOUTH SIDE. PROCEED S'LY ALONG SAID DIRT RD. 0.6 MILE, THEN HIKE E'LY 230'+/- TO SAID STATION LOCATED NEAR THE TOE OF SLOPE.