

GPS #: **0629**

Date Destroyed:

Date Revised: 7/1/1997

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 951/C-4

City / Location: Laguna Niguel

Scale Factor: 0.99996018

Ellipsoid Red. Factor: 1.00000134

Combination Factor: 0.99996152

Convergence Angle: -00 49 13.77132

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 32 00.65967	117 44 35.20808	2141009.819	6106680.252	-27.966
2007.00	33 32 00.67669	117 44 35.22435	2141011.56	6106678.90	

References: OCS SURVEY FILE # G93/94-13N

Description:

FD PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0629" FLUSH IN A.C. SURFACE - LOCATED IN ALISO WOODS CANYON REGIONAL PARK. FROM THE INTER OF ALICIA PKWY. AND AWMA RD., PROCEED W'LY ALONG AWMA RD. 0.1 MILE TO AN OPEN COUNTY PARK GATE. PROCEED THRU SAID GATE AND CONTINUE S'LY ALONG A.C. RD. 2.1 MILES TO SAID STATION LOCATED 5.'+/- E'LY OF THE W'LY EDGE OF THE A.C. RD.

