

GPS #: 0659

Date Destroyed:

Date Revised: 7/1/1997

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 951/C-6

City / Location: Laguna Niguel

Scale Factor: 0.99995923

Ellipsoid Red. Factor: 1.00000277

Combination Factor: 0.99996200

Convergence Angle: -00 49 08.57560

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 01.58491	117 44 25.75303	2135027.912	6107395.170	-57.792
2007.00	33 31 01.60191	117 44 25.76903	2135029.65	6107393.84	

References: OCS SURVEY FILE # G93/94-13N

Description:

FD PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0659" FLUSH IN A.C. SURFACE - LOCATED IN ALISO WOODS CANYON REGIONAL PARK. FROM THE INTER OF ALICIA PKWY. AND AWMA RD., PROCEED W'LY ALONG AWMA RD. 0.1 MILE TO AN OPEN COUNTY PARK GATE. PROCEED THRU SAID GATE AND CONTINUE S'LY ALONG A.C. RD. 3.35 MILES TO A "T" INTER, TURN RIGHT AND CONTINUE ALONG A.C. RD. 0.15 MILE TO SAID STATION LOCATED IN A.C. RD.

