

**GPS #:** 0660

Date Destroyed:

Date Revised: 7/1/1997

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 951/D-6

City / Location: Laguna Niguel

Scale Factor: 0.99995924

Ellipsoid Red. Factor: 1.00000026

Combination Factor: 0.99995951

Convergence Angle: -00 48 58.15925

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 31 02.61103	117 44 06.79758	2135108.718	6109001.331	-5.410
2007.00	33 31 02.62797	117 44 06.81359	2135110.45	6109000.00	

References: OCS SURVEY FILE # G93/94-13N

## Description:

FD PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0660" FLUSH IN A.C. SURFACE - LOCATED IN ALISO WOODS CANYON REGIONAL PARK. FROM THE INTER OF ALICIA PKWY. AND AWMA RD., PROCEED W'LY ALONG AWMA RD. 0.1 MILE TO AN OPEN COUNTY PARK GATE. PROCEED THRU SAID GATE AND CONTINUE S'LY ALONG A.C. RD. 3.35 MILES TO A "T" INTER, TURN LEFT TOWARD THE WATER DISTRICT PLANT AND CONTINUE ALONG A.C. RD. 0.15 MILE TO SAID STATION LOCATED IN A.C., 13'+/- W'LY FROM THE MOST W'LY CORNER OF A 3-DOOR METAL GARAGE NORTH OF A STORAGE TANK AND 9.5'+/- E'LY FROM THE EDGE OF A.C. PAVEMENT.

