

**GPS #:** 0671

**Date Destroyed:** 7/25/2000

**Date Revised:** 7/1/1997

**Benchmark Designation:**

**OCS Index Map:** 6LA

**Page/Grid:** 951/B-7

**City / Location:** Laguna Beach

**Scale Factor:** 0.99995898

**Ellipsoid Red. Factor:** 1.00000458

**Combination Factor:** 0.99996357

**Convergence Angle:** -00 49 27.48210

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 45.31416	117 45 00.15867	2133425.269	6104458.885	-95.768
2007.00	33 30 45.33118	117 45 00.17474	2133427.01	6104457.55	

**References:** OCS SURVEY FILE # G93/94-13N

**Description:**

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD PUNCHED SPIKE AND 1" TAG STAMPED "3047" FLUSH IN A.C. SURFACE - LOCATED FROM THE INTER OF PACIFIC COAST HWY. AND COUNTRY CLUB RD. (ENTRANCE TO ALISO CREEK RESORT AND GOLF COURSE), PROCEED NE'LY ALONG COUNTRY CLUB RD. 0.15 MILE TO SAID STATION LOCATED ALONG SAID RD., 11'+/- N'LY FROM THE S'LY EDGE OF SAID RD. AND 100'+/- SW'LY FROM ITS JUNCTION WITH THE A.C. RD. TO ALISO CREEK RESORT.