

GPS #: **0672**

Date Destroyed:

Date Revised: 11/13/2002

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 951/B-7

City / Location: Laguna Beach

Scale Factor: 0.99995899

Ellipsoid Red. Factor: 1.00000425

Combination Factor: 0.99996325

Convergence Angle: -00 49 26.06209

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 45.91870	117 44 57.57456	2133483.221	6104678.534	-88.897
2007.00	33 30 45.93571	117 44 57.59061	2133484.96	6104677.20	

References: OCS SURVEY FILE # G93/94-13N, CR 2002-1722

Description:

FD PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0672" FLUSH IN A.C. SURFACE - LOCATED FROM THE INTER OF PACIFIC COAST HWY. AND COUNTRY CLUB RD. (ENTRANCE TO ALISO CREEK RESORT AND GOLF COURSE), PROCEED NE'LY ALONG COUNTRY CLUB RD. 0.2 MILE TO SAID STATION LOCATED ALONG SAID RD., 6'+/- SE'LY FROM THE NW'LY EDGE OF SAID RD. AND 150'+/- NE'LY FROM ITS JUNCTION WITH THE A.C. RD. TO ALISO CREEK RESORT.

