

**GPS #:** **0698R1**

Date Destroyed:

Date Revised: 10/16/2006

Benchmark Designation:

OCS Index Map: 6LA

Page/Grid: 971/B-1

City / Location: Laguna Beach

Scale Factor: 0.99995870

Ellipsoid Red. Factor: 1.00000045

Combination Factor: 0.99995915

Convergence Angle: -00 49 25.16257

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 30 26.44390	117 44 55.93764	2131512.995	6104788.819	
2007.00	33 30 26.46097	117 44 55.95375	2131514.74	6104787.48	

References: OCS SURVEY FILE # G93/94-13N, CR 2002-1723, CR 2006-0455

## Description:

FD PUNCHED SPIKE AND CALTRANS WASHER FLUSH, IN LIEU OF PUNCHED SPIKE AND 1 1/2" BRASS O.C.S. TAG STAMPED "GPS 0698". MONUMENT WAS RESET PER CORNER RECORD # 2002-1723. MONUMENT IS LOCATED FROM THE INTER OF PACIFIC COAST HWY. AND CROWN VALLEY PKWY., PROCEED NW'LY ALONG PACIFIC COAST HWY. 1.95 MILES TO SAID STATION LOCATED AT THE TIP OF A PAINTED LEFT TURN ARROW IN THE LEFT TURN LN. ON NORTH BOUND PACIFIC COAST HWY. AT ADDRESS #31351 ALONG SAID HWY.

