

GPS #: **0728**

Date Destroyed:

Date Revised:

Benchmark Designation:

OCS Index Map: 6LC

Page/Grid: 833/F-7

City / Location: Unin., Orange County

Scale Factor: 0.99997603

Ellipsoid Red. Factor: 0.99976332

Combination Factor: 0.99973936

Convergence Angle: -00 42 56.43073

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

NO PHOTO

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 42 49.21645	117 33 08.53199	2205780.863	6165619.775	4947.631
2007.00	33 42 49.23326	117 33 08.54769	2205782.58	6165618.47	

References: RS 92-1119

Description:

FD 2" I.P. WITH OCS BRASS DISK STAMPED "RUTH 11-92" UP 0.3', LOCATED FROM THE INTER OF SANTIAGO CANYON RD. AND SILVERADO CANYON RD., PROCEED E'LY ALONG SILVERADO CANYON RD. 4.8 MILES TO THE END OF PUBLIC RD. WITH A LOCKED IRON GATE(U.S. FOREST LOCK). PASS THRU GATE AND CONTINUE ALONG RD. 7.7 MILES TO A FORK WITH THE MAIN DIVIDE RD. TAKE THE RIGHT FORK AND CONTINUE S'LY UPHILL 1.6 MILES TO A FORK IN RD. AND A LARGE GRADED TURNOUT ON LEFT (0.2 MILE PAST MICROWAVE TOWERS RD.). PARK IN TURNOUT. SAID MONUMENT IS LOCATED ON THE KNOLL SW OF FORK AND IS ADJACENT TO THE "3S04" MILE MARKER #18, 10'+/- UP FROM GRADED RD., NE'LY OF LARGE BOULDERS AT THE TOP OF KNOLL AND 3.7' SOUTH OF A BUSH.

