

GPS #: 0742

Date Destroyed: 9/20/1995

Date Revised:

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 922/G-3

City / Location: Unin., Orange County

Scale Factor: 0.99996372

Ellipsoid Red. Factor: 0.99997264

Combination Factor: 0.99993637

Convergence Angle: -00 45 24.94359

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 35 06.85559	117 37 38.79241	2159343.135	6142174.393	577.246
2007.00	33 35 06.87247	117 37 38.80821	2159344.86	6142173.08	

References: OCS SURVEY FILE # 93/94-2

Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD 3 1/2" ALUMINUM DISK STAMPED "WILLIAM & SHMID SMC-024 1988" LOCATED FROM THE INTER OF OSO PKWY. AND ANTONIO PKWY., PROCEED N'LY ALONG ANTONIO PKWY. 100'+/- TO A DIRT RD. ON THE E'LY SIDE OF THE PKWY. PROCEED E'LY ALONG THE DIRT 0.15 MILE TO A "Y" INTER WITH ANOTHER DIRT RD. PROCEED SE'LY UPHILL ON THE DIRT RD. 0.1 MILE TO THE SAID MONUMENT.