

**GPS #:** 0756

Date Destroyed: 7/9/1999

Date Revised:

Benchmark Designation: 3B 58A-82

OCS Index Map: 6LA

Page/Grid: 972/B-4

City / Location: San Juan Capistrano

Scale Factor: 0.99995727

Ellipsoid Red. Factor: 1.00000362

Combination Factor: 0.99996089

Convergence Angle: -00 47 00.85724

*Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.*

Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 28 39.25055	117 40 33.33396	2120367.504	6126874.067	-75.640
2007.00	33 28 39.26745	117 40 33.35003	2120369.23	6126872.73	

References: OCS FILE # RD 95/6-20S, GEODETIC UNIT

## Description:

REPORTED DESTROYED (SEE DATE IN DESTROYED BOX) - ORIGINAL DESCRIPTION BEING: FD OCS 3 3/4" ALUMINUM DISK STAMPED "3B 58A-82" UP 1.0', LOCATED FROM THE RAILRD. CROSSING AT AVENIDA AEROPUERTO, TRAVEL S'LY ALONG RAILRD. TRACKS 0.3 MILE TO A WOOD PLANK COVERED CULVERT AT THE SE CORNER OF A TRAILER PARK. CONTINUE S'LY ALONG RAILRD. TRACKS 200' TO A CONTROL BOX ON A POST, 4' X 2' STEEL BOX, AND A TELEGRAPH POLE 35' W'LY OF TRACKS. BENCH MARK IS 18.4' NE FROM THE TELEGRAPH POLE, 9.6' NE OF THE CONTROL BOX POST AND 31' WEST OF THE WEST RAIL OF THE W'LY SET OF TRACKS, SET IN THE TOP OF A CONC. POST, FLUSH WITH THE GROUND.