

GPS #: **0757**

Date Destroyed:

Date Revised: 8/23/1996

Benchmark Designation:

OCS Index Map: 6LB

Page/Grid: 972/B-4

City / Location: San Juan Capistrano

| | |
|------------------------|-----------------|
| Scale Factor: | 0.99995753 |
| Ellipsoid Red. Factor: | 1.00000291 |
| Combination Factor: | 0.99996044 |
| Convergence Angle: | -00 46 52.11706 |

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



| Epoch Adjustment | Latitude | Longitude | Northing (ft) | Easting (ft) | Ellipsoid Height (ft) |
|------------------|----------------|-----------------|---------------|--------------|-----------------------|
| 1991.35 | 33 29 00.33776 | 117 40 17.42877 | 2122480.310 | 6128250.208 | -60.814 |
| 2007.00 | 33 29 00.35469 | 117 40 17.44497 | 2122482.04 | 6128248.86 | |

References: OCS FILE # RD 95/6-20S, GEODETIC UNIT

Description:

FD PUNCHED SPIKE AND 1 1/2" OCS TAG FLUSH IN A.C. LOCATED 20' +/- WEST OF A BLOCK WALL, AND 32' +/- NORTH OF A CHAIN LINK FENCE IN THE SE CORNER OF THE PARKING LOT OF JEROME THORNSLEY EDUCATION CENTER AT 32972 CALLE PERFECTO, NORTHWESTERLY 50' +/- OF RAILROAD TRACKS AND EAST OF SAN JUAN CREEK.

