

GPS #: 0758

Date Destroyed:
Date Revised: 8/23/1996
Benchmark Designation: 3LL-3-78
OCS Index Map: 6LA
Page/Grid: 972/A-3
City / Location: San Juan Capistrano

Scale Factor: 0.99995759
Ellipsoid Red. Factor: 1.00000055
Combination Factor: 0.99995814
Convergence Angle: -00 47 17.28573

Factors and Convergence Angle based on the 1991.35 Epoch Adjustment positions.



Epoch Adjustment	Latitude	Longitude	Northing (ft)	Easting (ft)	Ellipsoid Height (ft)
1991.35	33 29 05.11687	117 41 03.23017	2123016.438	6124377.984	-11.437
2007.00	33 29 05.13382	117 41 03.24656	2123018.17	6124376.62	

References: OCS FILE # RD 95/6-20S, GEODETIC UNIT

Description:

DESCRIBED BY OCS 2003 - FOUND 3 3/4" OCS ALUMINUM BENCHMARK DISK STAMPED "3LL-3-78", SET IN THE NORTHWESTERLY CORNER OF A 4 FT. BY 11 FT. CONCRETE CATCH BASIN. MONUMENT IS LOCATED IN THE SOUTHWESTERLY CORNER OF THE INTERSECTION OF WESTBORNE DRIVE AND DEL OBISPO STREET, 45.8 FT. WESTERLY OF THE CENTERLINE OF DEL OBISPO, 111 FT. SOUTHERLY OF THE CENTERLINE OF WESTBORNE AND 3.8 FT. WESTERLY OF THE CURB FACE. MONUMENT IS SET LEVEL WITH THE SIDEWALK.

